

Waterfront Park Stage Gazebo Project Addendum No. 2

Project Contacts

Rodney Due	Director of Public Works	rdu@myseminole.com
Vinny Torres	Facilities Maintenance Supervisor	vtorres@myseminole.com

Questions and Answers

- I noticed a tree in the way, based off where the sidewalk meets the original sidewalk. Is it the idea to remove/relocate this tree or work around it? **Yes, remove and relocate if tree is in the way.** If removing, who would be responsible? **Contractor is responsible for any landscape, irrigation, stormwater pipe, or electric that needs to be removed, replaced, or damaged.**
- Is there a certain number of electrical receptacles wanted for the gazebo? **Three (3) receptacles plus a gang box for sound equipment as discussed during the pre-bid meeting. It was suggested to look at the bandshell in City Park located at 7464 Ridge Rd.**
- The small plans provided with the project details call out for 4' sidewalks. The rest of the park utilizes 6' sidewalk, which is a much more common size in a commercial setting, especially where wheelchairs will be used. Does the City want 6' sidewalks and ADA ramps or keep the 4' like the plans state? **The sidewalks within Waterfront Park vary in width, please bid according to the plans (4' wide).**

Bid Alternative #1

Provide a line-item cost for six (6) foot wide ADA-compliant ramps and access routes.